

# Installation and Commissioning Plans for the jFEX

Katharina Bierwagen


# Agenda

- Introduction
- jFEX Status
- Hardware Availability
- Surface Test Facility
- Installation
- Commissioning
- Summary

# Introduction


- jet, large tau, energy sums
- 6 modules, 1 ATCA shelf
- 4 x UltrascalePlus
- Up to 120 MGTs each
- 24 MiniPODs
- Power and control mezzanines

jFEX functionality – Block Diagram



# jFEX Status

- Final Design Review took place end of May
  - Firmware: May 29
    - <https://indico.cern.ch/event/728398/>
  - Hardware: May 30
    - <https://indico.cern.ch/event/728400/>
- Green light for producing the jFEX Pre-Production modules on June 12
- Ongoing PCB production
- Order of all components placed
- Expect delivery from assembly company: beginning of October
- Firmware
  - Ongoing integration of infrastructure firmware (MGTs, board control, IOs and etc.) and algorithms



# Hardware Availability (Plan)

- jFEX First Prototype – Currently at CERN (STF)
  - Equipped with one UltraScale FPGA
- jFEX Final Prototype – Currently in Mainz
  - Equipped with four UltraScale+ FPGAs
- jFEX Pre-Production Module – Available from November 2018 onwards
  - Pre-Production module will later be used as spare
- jFEX Production Modules – Available from May 2019 onwards
  - 9 (+ 1) modules
    - 6 to be installed
    - 3 (+ 1) spares

# Surface Test Facility (1)

**Final Prototype = Pre-Production Module = Production Module**

- No hardware changes are foreseen from prototype to production module
- Initial integration tests with other systems can start at anytime with Final Prototype
  - And with Pre-Production by November
- Combined tests with TREX in Heidelberg this week
- Combined tests with ROD (Hub) to take place soon

# Surface Test Facility (2)

- Setup ready for tests with jFEX First Prototype and FTM since July
  - Tests of optical links, TTC clock reception, IPBus and etc. were performed
  - jFEX Final Prototype is currently in Mainz, but will be shipped back to CERN soon
- Aim to test and validate full module functionality at STF except:
  - Concurrent operation of all calorimeter inputs, all modules
  - Channel mapping
  - Final timing calibration



# Surface Test Facility

## Pre-Production Module

- Validation of Pre-Production module will take place at the STF
  - Smoke tests and basic validation of board optical/electrical links (IBERT) to be done in Mainz
  - Validation of all optical/electrical inputs/outputs simultaneously (IBERT and formatted data)
  - Power consumption under full load
    - Ripple measurement
    - Thermal dissipation
  - LHC clock reception
    - MGTREF clock jitter measurement
  - Validation of the backplane high-speed links
    - Readout and TTC data
    - Latency measurement
    - IPMC
- Firmware consolidation
  - Tests with integrated firmware (infrastructure and algorithms)
  - Latency measurement
  - Combined tests with other parts of the system



# Surface Test Facility

## Production Module

- Initial production modules acceptance tests will take place in Mainz
  - Smoke tests and basic validation of board optical/electrical links (IBERT)
- Finalization of production modules acceptance tests on ATCA crate with HUB/ROD and/or FTM
  - Same test list of the Pre-Production module
- Full slice test from Latome/TREX via jFEX to Topo
  - As much as possible inputs
    - Formatted data
  - With all possible infrastructure parts
    - Hub/ROD, FELIX, IPBus, DCS and etc.
  - Final evaluation on power consumption and cooling with closed shelf
- Integration with “L1Calo STF partition”

# USA15 Installation (1)

- jFEX connections

- LATOME
- TREX
- FOX
- Hub/ROD
  - FELIX

Scheduled to be installed  
before jFEX


- Topo

- Installation schedule for December 2019

- Initial tests

- Verification of board functioning after transport
- Establishment of board communication and control
  - IPbus and DCS
- Integration tests with HUB/ROD
- Combined tests with calorimeters

similar to what was done in  
STF during 2018 and 2019



# USA15 Installation (2)

- Expect to be available for cable installations and mapping tests from June 2019 (1 jFEX sliding)
- Final installation (full set of modules) starting in November 2019
- Followed by 3 months re-integration & commissioning

# Commissioning

- Final validation of (FOX) input mapping
- Integration with ATLAS partition
- Online monitoring
- Combined tests with calorimeter
- Timing calibrations
- Pre-beam commissioning with cosmics
- Commissioning with beam
- Validation with bit-wise simulation
- Cross-comparison with legacy system

# Summary

- Ongoing production of the jFEX Pre-Production module
- Pre-Commissioning to take place during 2018 and 2019 at the STF
  - Setup ready on the STF for jFEX
  - Finalization of production modules acceptance tests
- Final installations in USA15 scheduled for November 2019

# jFEX Schedule

