



jFEX/L1Topo Installation

Uli / Mainz

What's Installation ?

- Install hard and heavy infrastructure and services
 - Racks
 - Cooling
 - Power
 - Shelves
 - PCs
- Install (fibre) cabling, terminate into RTMs (with dust caps)
- Provide basic services
 - Networking
 - Module control
 - Debug tools
 - Some level of environmental monitoring
 - Safety mechanisms
- Slide in modules
- Many threads in parallel:
 - Validate connectivity
 - Complete services
 - Get firmware, software, databases ready for physics



Requirements for module installation

- All heavy items in
- Some connectivity available
 - One module will be the first one with nothing to talk to
 - Basic networking
- We have many layers of protection
 - FPGA unconfigure on over-temperature
 - Local monitoring on IPMC
 - Data from IPMC into DCS
 - I2C based monitoring via module controller (Zynq)
 - Zynq I2C data can be read out directly from Zynq PS
 - Same data read out via IPbus
 - Some of that needs to be available before 1st module goes in
- Need some personal equipment laptop, JTAG, meters, ...

Grow the system

- No desire to chuck large numbers of modules into freshly installed shelves
 - Start with individual modules, prototype/pre-production first
 - Assume that possibly jFEX-L1Topo might be the first interface to be tested under ground
 - Need to find out a few facts about MUCTPI and CTP
 - Include further module types as they arrive
-
- The assumption here is that for quite a while activities in USA15 and STF are being run concurrently
 - Reduce clashes between various test requirements
 - Few people available for installing/maintaining modules & systems
 - Ideally plenty of people working at both P1 and STF remotely
 - Full shelf of modules ($3 \times \text{L1Topo}$, $6 \times \text{jFEX}$) operation at P1 is certainly a milestone, though not an exciting one. Expect shelves full of modules to be in full operation at STF prior to that.